

ANNE ARUNDEL COUNTY
Department of Public Works
Public Meeting Summary

TO: Matt Diehl

FROM: Maribel Moore

DATE: November 9, 2018

PHONE NO: (410) 222-7565

Selby Sewer Service Area Piping Upgrade

Anne Arundel County Department of Public Works is currently in design to upsizing the small diameter low pressure sewer in 2nd Avenue, 980 LF on Edgemont Street, 690 LF on Beach Drive Blvd, and 390 LF on Evelyn Gingell Avenue in the Selby Area. The project is being undertaken to maintain the serviceability of the low pressure sewer main. Current timeline for the entire project is that we anticipate to complete design and begin bidding the construction contract in the Summer of 2019. Construction NTP Fall of 2019 and Completion Spring of 2020.

Selby I and II SPS

Anne Arundel County Department of Public Works has completed design and award of the construction contract to upgrade to the Selby I & II Sewer Pump Stations to include replacement of wetwell pumps, controls and necessary appurtenances. In addition, in Selby I, we are replacing the generator and installing a permanent diesel bypass system. In Selby II, we are installing a generator and a valve vault. The upgrades are being done to comply with Maryland Department of Environment requirements for emergency storage, as well as insure that each station has the capacity to meet any future growth. Construction notice to proceed was given to the contractor on August 20, 2018. The contractor is expected to begin work onsite approximately mid-December or early January. Construction is expected to be completed August 20, 2019.

Re: S799211-Selby Sewer Service Area Piping Upgrade
November 13, 2018
Page 2 of 2